

Resolving the contribution of the uncoupled phycobilisomes to cyanobacterial pulse-amplitude modulated (PAM) fluorometry signals

Alonso M. Acuña¹ · Joris J. Snellenburg¹ · Michal Gwizdala¹ · Diana Kirilovsky² · Rienk van Grondelle¹ · Ivo H. M. van Stokkum¹

Received: 9 December 2014 / Accepted: 2 April 2015 / Published online: 19 April 2015
© The Author(s) 2015. This article is published with open access at Springerlink.com

Abstract Pulse-amplitude modulated (PAM) fluorometry is extensively used to characterize photosynthetic organisms on the slow time-scale (1–1000 s). The saturation pulse method allows determination of the quantum yields of maximal (F_M) and minimal fluorescence (F_0), parameters related to the activity of the photosynthetic apparatus. Also, when the sample undergoes a certain light treatment during the measurement, the fluorescence quantum yields of the unquenched and the quenched states can be determined. In the case of cyanobacteria, however, the recorded fluorescence does not exclusively stem from the chlorophyll *a* in photosystem II (PSII). The phycobilins, the pigments of the cyanobacterial light-harvesting complexes, the phycobilisomes (PB), also contribute to the PAM signal, and therefore, F_0 and F_M are no longer related to PSII only. We present a functional model that takes into

account the presence of several fluorescent species whose concentrations can be resolved provided their fluorescence quantum yields are known. Data analysis of PAM measurements on in vivo cells of our model organism *Synechocystis* PCC6803 is discussed. Three different components are found necessary to fit the data: uncoupled PB (PB_{free}), PB–PSII complexes, and free PSI. The free PSII contribution was negligible. The PB_{free} contribution substantially increased in the mutants that lack the core terminal emitter subunits allophycocyanin D or allophycocyanin F. A positive correlation was found between the amount of PB_{free} and the rate constants describing the binding of the activated orange carotenoid protein to PB, responsible for non-photochemical quenching.

Keywords Pulse-amplitude modulated (PAM) fluorometry · Fluorescence quantum yield · Non-photochemical quenching · Phycobilisome · Cyanobacteria

Electronic supplementary material The online version of this article (doi:10.1007/s11120-015-0141-x) contains supplementary material, which is available to authorized users.

✉ Rienk van Grondelle
rienk@few.vu.nl

✉ Ivo H. M. van Stokkum
i.h.m.van.stokkum@vu.nl

¹ Institute for Lasers, Life and Biophotonics, Faculty of Sciences, VU University Amsterdam, De Boelelaan 1081, 1081 HV Amsterdam, The Netherlands

² Institut de Biologie et Technologies de Saclay (iBiTec-S), Commissariat à l’Energie Atomique et aux Energies Alternatives (CEA), 91191 Gif-sur-Yvette, France

Abbreviations

APC	Allophycocyanin
Chl	Chlorophyll
C-PC	C-phycocyanin
FRP	Fluorescence recovery protein
NPQ	Non-photochemical quenching
OCP	Orange carotenoid protein
PAM	Pulse-amplitude modulated
PB	Phycobilisome
PC	Phycocyanin
PPc2	Phycobilisome–Photosystem II complex
PQ	Plastoquinone
PSI	Photosystem I
PSII	Photosystem II
rmse	Root mean square error
SNR	Signal-to-noise-ratio

Introduction

Chlorophyll *a* (Chl *a*) fluorescence carries important information about the primary photophysical processes taking place in the thylakoid membrane, including non-photochemical quenching (NPQ) (Baker 2008; Krause and Weis 1991; Papageorgiou and Govindjee 2004; van Grondelle 1985; van Grondelle et al. 1994). This is why Chl *a* fluorescence quenching analysis by the saturation pulse method has been extensively used in the study of photosynthetic organisms (Schreiber et al. 1995). Pulse-amplitude modulated (PAM) fluorometry is a sensitive tool which measures the fluorescence quantum yield ϕ_{F} in different sample states, e.g. quenched/unquenched. This has enabled in vivo characterization of the photosynthetic apparatus of *Synechocystis* PCC6803 (hereafter *Synechocystis*) in different light-acclimated states (Campbell et al. 1998; Kirilovsky 2007, 2014; Wilson et al. 2007). In the particular case of cyanobacteria, the recorded fluorescence originates from different sources: not only Chl *a* of photosystems (PSI and PSII) but also phycobilins, embedded in the antenna complexes, the phycobilisomes (PBs), contribute to the PAM signal (see Fig. 1 and reviews Campbell et al. 1998; Kirilovsky 2014).

Therefore, a mathematical model is needed in order to interpret the data correctly. Holzwarth et al. have already emphasized that PAM fluorescence data often get converted to the (Stern–Volmer) NPQ space via a simple, but by no means “innocent”, mathematical transformation $x(t) \rightarrow x^{-1}(t)$ leading to distorted kinetics (Holzwarth et al. 2013). Instead, a careful description of the hypothesized NPQ processes is essential. An example of such PAM modelling efforts is the kinetic model developed by Ebenhöh and co-workers for zeaxanthin-related NPQ in

plants and from which PAM curves could be simulated (Ebenhöh et al. 2011). However, systematic discrepancies between their simulations and experimental PAM data, in particular in the light to dark transition, have shown just how challenging it is to consistently reproduce the NPQ kinetics while validating strongly simplifying assumptions. In another attempt, the rapidly reversible component of NPQ and its dynamically controlled appearance/disappearance under low and strong actinic light conditions have been modelled by Zaks et al. (2012). Finally, models have been developed that combine detailed PSII and inter-photosystem electron transport with Calvin-cycle reactions (Laisk et al. 1997). In this article, we focus on cyanobacterial PAM studies in which the PB-related contribution to the PAM signal must first be resolved for, as long as it remains neglected, no solid statements on the PSII-specific activity can be formulated.

Phycobilisomes: the difference between cyanobacterial and plant signals

The phycobilisome is the cyanobacterial light-harvesting complex. In *Synechocystis*, the phycobilisomes are composed of six C-phycocyanin (C-PC) rods (see Fig. 2) each of which is composed on average of three disc-shaped hexamers (12 bilins per hexamer) (Arteni et al. 2009) that absorb at ca. 620 nm and whose fluorescence maxima lie within the range 640–650 nm (Glazer et al. 1983). These C-PC rods are linked to the three allophycocyanin (APC) core cylinders arranged such that their respective centres draw a triangle with one of its sides facing the thylakoid membrane (Bryant et al. 1979). In each of the core cylinders, there are four trimer discs (six bilins per trimer). Each monomer of the trimer is made of two polypeptidic units called α^{APC} and β^{APC} ; their absorption peak lies at 650 nm and they emit at 660 nm, hence why they are referred to as APC₆₆₀. However, within the basal cylinders, and in the proximity of the membrane, there are (i) one trimer in which one of the three monomers is not formed by one β^{APC} and one α^{APC} -unit but one β^{APC} and one ApcD-unit instead (previously called $\alpha^{\text{APC-B}}$), (ii) a second trimer that also differs from the $(\alpha\beta)_3$ conformation, where the β^{APC} is replaced by an ApcF ($\beta^{\text{APC-}\beta 18}$) and the α^{APC} by an ApcE (the core-membrane linker, α^{Lcm}) (see reviews by Adir 2005; MacColl 1998). Even though the linker proteins do not contain pigments themselves, they have been shown to play a role in fine-tuning rod energy absorption and energy transfer capabilities (David et al. 2011)

NPQ in *Synechocystis*

PB-containing cyanobacteria (such as *Synechocystis*) have developed different non-photochemical-quenching photo-protective mechanisms. The two principal ones are state




Fig. 1 Emissive spectra of Chl *a* and PB in vivo. The spectral overlap within the detection region of typical PAM setups is shown in red




Fig. 2 The different emissive species giving rise to a cyanobacterial PAM signal [see Eq. (3)] are characterized by their respective quantum yields in different light-acclimated states. Phycobilisomes are represented as six blue rods attached to three grey cylinders as the core. Two rectangular units represent an open (dark green) or closed (red) PSII-dimer. PBs can be bound to a PS or not. The index j indicates whether the emissive species is an uncoupled PB

(a $j = PB$) a single PB–PSII complex (PPc2) (b $j = PPc2$). $j = PB$ can still result in two different states if, for instance, a minimal amount of light (black bar) or high-light (blue–green bar) is shone onto the sample: unquenched (c $l = u$) or quenched (d $l = q$). The index k indicates whether the PSII is open (e $k = o$) or, in case a saturation pulse fully reduces the PQ pool, closed (f $k = c$)

transitions and OCP-related NPQ. The former denotes the organism's ability to distribute excitation energy between PSI and PSII as a function of the redox status of the linear electron transport chain (Fork and Satoh 1986; Kirilovsky et al. 2014; Mullineaux and Allen 1990; Vernotte et al. 1990). When cyanobacteria cells are illuminated with orange light, principally absorbed by PBs, the PQ pool becomes more reduced and a transition to state 2 is induced accompanied by a decrease of fluorescence. In contrast, blue light, principally absorbed by chlorophyll, induces a transition to state 1 and increase of fluorescence. In darkness, *Synechocystis* are known to be in state 2, since the PQ pool is reduced via the respiration. Thus, illumination of dark-adapted cells with low intensities of blue light provokes a transition to state 1. Modelling state transitions, however, goes beyond the scope of this study. Instead, we will focus on the second mechanism, the OCP-related NPQ. In higher plants, the energy-related component of NPQ is induced by a pH-gradient (Wraight and Crofts 1970) and involves the xanthophyll cycle (Demmig et al. 1987) and/or the PsbS protein protonation (Funk et al. 1995; Li et al. 2000). In contrast, in cyanobacteria, an equivalent mechanism which reduces the energy arriving to the reaction centres is triggered when the orange carotenoid protein (OCP) is photoactivated and binds to the phycobilisomes (Gwizdala et al. 2011; Wilson et al. 2006, 2008). Binding only occurs if the non-active orange form OCP^o is

photo-converted to the red form OCP^r (OCP^o → OCP^r conversion) (Gwizdala et al. 2011; Wilson et al. 2008). Thus, when strong blue–green light is absorbed by the carotenoid, OCP^r is first formed, and then it attaches to the PB core leading to most of the excitation energy being dissipated and not reaching the RCs. Since energy dissipation occurs at the PB level, we do not model NPQ at the dark and at the maximum fluorescence level differently, as it has been proposed for plants (Härtel and Lokstein 1995). Detaching of OCP is assisted by yet another protein: the fluorescence recovery protein (FRP) (Boulay et al. 2010; Sutter et al. 2013). The OCP/FRP ratio in the cell can be considered as the regulator of the induction of heat dissipation (Gwizdala et al. 2013).

PAM fluorometry

Both photochemistry yields and NPQ induction can be followed by PAM fluorometry. A PAM instrument is able to trace changes of the yield of fluorescence under different light conditions. Typically, three levels of fluorescence, called F_0 , F_M and F_S , are observed in a PAM trace. The minimal fluorescence level (F_0) is recorded, while the photosynthetic organism is dark-adapted and all the PSII centres are open (the primary quinone Q_A is oxidized). The intensity of the modulated measuring light (in PAM 101–103: $\lambda_m = 650$ nm; dual-PAM: $\lambda_m = 630$ and

440–460 nm) used to determine F_0 is very low (non-actinic) in order to avoid photochemistry, which could yield a biased minimum. The F_M level is induced by a saturation pulse typically of $>2000 \mu\text{mol}$ of photons $\text{m}^{-2} \text{s}^{-1}$. Its duration (200–1000 ms) ensures multiple turnovers and a transient closure of the reaction centres (Q_A reduced). Therefore, F_M corresponds to the state of fully closed PSII reaction centres (Q_A reduced). During this state, the yield of photochemistry is minimal, i.e. the recorded fluorescence level is maximal (Papageorgiou et al. 2007). The steady-state fluorescence level (F_S) is measured under continuous illumination and depends on the fraction of reduced Q_A . Other parameters, such as the variable fluorescence, F_V , are derived from the measured values. F_V is defined as the difference between the maximal fluorescence level, F_M , and the darkness fluorescence level (Butler 1978), F_0 : $F_V = F_M - F_0$ (see Fig. S1).

The phycobilins of the PBs, not present in higher plants, lead to a major difference in the PAM signal: since the Chl *a* (PSII) and the phycobilin (PB) fluorescence spectra overlap (see Fig. 1) precisely within the spectral region where fluorescence is typically collected ($\lambda_{\text{det}} > 700 \text{ nm}$), $F_{0,\text{cyano}}$ lies higher than the F_0 -level recorded in plants:

$$F_{0,\text{cyano}} = F_{0,\text{PSII}} + F_{0,\text{PB}}, \quad (1)$$

where $F_{0,\text{PSII}}$, $F_{0,\text{PB}}$ are, respectively, the fluorescence from PSII Chl *a* and from PBs. $F_{0,\text{PB}}$ also adds to the maximal fluorescence:

$$F_{M,\text{cyano}} = F_{M,\text{PSII}} + F_{0,\text{PB}}. \quad (2)$$

The ratio Chl *a*/phycobilin fluorescence depends on the wavelength λ_m of the measuring light. The amount of Chl *a*-related fluorescence when induced by blue light (exciting more the Chl *a* than the bilins) is greater than it is when orange light (specific to phycocyanin) is used instead. All measurements shown in this article were carried out using a PAM 101–103 instrument with red measuring light ($\lambda_m = 650 \text{ nm}$) which yields an intermediate situation (Campbell et al. 1998; Kirilovsky 2014).

A model to resolve several contributions to a cyanobacterial PAM signal

We propose a model that determines the $F_{0,\text{PB}}$ -related contribution to the PAM signal. In this way, one could resolve the PAM-dynamics strictly related to PSII. Our model is based on the fundamental assumption that the fluorescent species' spectral properties are independent from its concentration in the sample. Any given PAM signal J_{PAM} can then be written as the product of an emissive species j , (spectrally) characterized by its fluorescence quantum yield Φ_j , multiplied by its

concentration c_j (which may or may not be time-dependent). Additionally, fluorescent species may be unquenched (dim blue light regime) or quenched (strong blue light regime).

A cyanobacterial sample will expectedly contain more than only one fluorescent species, so the PAM signal then becomes a linear superposition of the fluorescence originating from each one of the species. Furthermore, J_{PAM} depends on the light intensity of the measuring light, $I(t)$, and a set of model parameters $\mathbf{P} = (P_1, P_2, P_3, \dots)$ which we will define further below (see “Time evolution” section). Thus, the general expression is

$$J_{\text{PAM}}(I(t); \mathbf{P}) = \sum_{jkl} c_{jkl}(t) \times \Phi_{jkl}, \quad (3)$$

where the additional indices k and l represent different light-acclimated states; k takes into account whether PSII is open or closed and l stands for either a quenched or an unquenched species (see Fig. 2).

As a first example, consider two different species: let the first one be a phycobilisome–Photosystem II complex, abbreviated PPc2, while the second one, denoted PB_{free} , represents either completely free PB or PB non-functionally bound to membranes and finally PB that do not transfer energy efficiently to the PS and therefore have a long fluorescence lifetime. Note that the PPc2 contribution contains both emission from Chl *a* and from the PB attached to PSII.

Defining the time-independent, relative concentrations as c_2 (PPc2) and γ (PB_{free}) and using Eq. (3), it follows for $F_{0,\text{cyano}}$ and $F_{M,\text{cyano}}$:

$$F_{0,\text{cyano}} = c_2 \times \phi_{\text{PPc2},o,u} + \gamma \times \phi_{\text{PB},u}, \quad (4)$$

$$F_{M,\text{cyano}} = c_2 \times \phi_{\text{PPc2},c,u} + \gamma \times \phi_{\text{PB},u}. \quad (5)$$

Therefore, a model that aims to estimate the two unknown concentrations c_2 and γ needs a priori knowledge with respect to the quantum yields $\phi_{\text{PB},u}$, $\phi_{\text{PPc2},o,u}$ and $\phi_{\text{PPc2},c,u}$. Provided the latter are known, Eqs. (4)–(5) simply build a system of two equations with two unknowns.

This observation brings us to one of the fundamental assumptions in this article: the constant values for the fluorescence quantum yields of each species displayed in Table 1. These are derived from fluorescence lifetimes and emission spectra obtained from target analysis of time-resolved experiments. From streak camera studies performed on whole cells of *Synechocystis* combined with global and target analysis, the fluorescence lifetimes and emission spectra of the species present in the cell have been estimated (Tian et al. 2011, 2012, 2013). Table 1 thus provides the set of constant values needed to solve the system, and estimate the unknown concentrations. The numbers in this table should be considered an educated guess based upon

Table 1 Normalized estimates of each of the emissive species’ fluorescence quantum yields as determined from time-resolved spectroscopy and global and target analysis

	Unquenched	Quenched
Free PB	1	0.105
Free PSII (closed)	0.519	–
Free PSII (open)	0.036	–
Free PSI	0.023	–
PPc2 (closed)	0.502	0.189
PPc2 (open)	0.161	0.100
PPc1	0.106	0.060

the literature. The sensitivity of the results to these numbers has been investigated as well.

Results and discussion

Parameter estimation from simulated data

Using the model described above, we first simulate data assuming a certain amount of noise and a given saturation pulse frequency (*spf*). Since the range of values for both quantum yields and relative concentrations is [0,1], we introduce a scaling factor that matches the absolute scale of the fluorescence recorder used during the experiment. Figure S2 shows simulated data with a noise level of 0.01 and a pulse every 50 or 20 s. The parameters were set to $\gamma = 0.10$ and *scale* = 2000. This places the F_0 level at $(0.10 \times \mathbf{1} + 0.90 \times \mathbf{0.161}) \times 2000 = 488$ arbitrary units (bold numbers from Table 1).

Fitting the simulated data yielded the following parameters: (a) *spf* (50 s)⁻¹: $\gamma = (0.1003 \pm 0.004)$; *scale* = (1998.2 ± 2.5) and (b) *spf* (20 s)⁻¹: $\gamma = (0.1002 \pm 0.003)$; *scale* = (1999.0 ± 1.9) . The relative errors of the estimated parameters improved after increasing the *spf* (due to better sampling of the closed state). Hence, in an experiment where F_M should be determined precisely, one could increase the frequency at which the sample gets saturated. However, an F_M level decrease has been reported due to NPQ induced by the saturation pulses; this has been indeed observed in *Chlamydomonas* and *Synechocystis* (Schreiber et al. 1995) so extra attention should be paid to this effect when increasing the *spf* in quenching experiments and analysis on both plants and cyanobacteria.

Adding a PSII_{free} component

So far we have considered only two different contributions. We now consider a third species: PSII_{free}, i.e. PSII which is

not coupled to any PB. Let f_2 be its relative concentration. Expanding Eq. (3) the PAM signal of such a sample reads

$$J_{PAM}(I(t); PPc2, PB_{free}, PSII_{free}) = \begin{cases} \gamma \times \phi_{PB,u} + c_2 \times \phi_{PPc2,o,u} + f_2 \times \phi_{PSII,o} & t \neq t_{sat} \\ \gamma \times \phi_{PB,u} + c_2 \times \phi_{PPc2,c,u} + f_2 \times \phi_{PSII,c} & t = t_{sat} \end{cases} \quad (6)$$

Two major differences should be noticed: first, the new species, PSII_{free}, is spectrally characterized by the quantum yield ϕ_{PSII} which is not the same if the photosystem is attached to a PB antenna: $\phi_{PPc2} \neq \phi_{PSII}$. Second, the difference between the first and the second line in Eq. (6) lies in whether or not at a given time point t a saturation pulse was applied (denoted by t_{sat}). If applied, such a pulse causes a shift in the PSII population which affects the quantum yield: for $t = t_{sat}$, all PSII adopts a *closed state* (note the index c instead of o).

Just as in Eqs. (4) and (5), the contribution to the $F_{0,cyano}$ and $F_{M,cyano}$ in the case of these three components can be written as follows (see Table 1 for quantum yield values):

$$F_{0,cyano} = \gamma \times \phi_{PB,u} + c_2 \times \phi_{PPc2,o,u} + f_2 \times \phi_{PSII,o}, \quad (7)$$

$$F_{M,cyano} = \gamma \times \phi_{PB,u} + c_2 \times \phi_{PPc2,c,u} + f_2 \times \phi_{PSII,c}. \quad (8)$$

This time, Eqs. (7)–(8) build a system of *two* equations and *three* unknowns. This leads to *degeneracy* of the solutions, i.e. given this amount of information, more than only one set of parameters c_2, f_2, γ are possible solutions of the system. A unique solution cannot be found unless additional conditions are introduced.

NPQ

In the last section, we introduced a PAM model that is useful with two unquenched components only. However, during a PAM experiment, a second state, the quenched state, can be induced. A model of cyanobacterial NPQ is then needed if PAM measurements carried out under NPQ-inducing light conditions should be parameterized. A kinetic model of OCP-related NPQ has been developed by Gorbunov et al. (2011) in which a light-dependent reaction is responsible for the conversion of OCP^o to OCP^f which then can bind to the PB core and subsequently induce NPQ. A model reproducing the OCP^o → OCP^f conversion, the binding of OCP^f to PB and the FRP-related detaching of OCP is explained in detail in the SI [see “Derivation of the quenching and recovery dynamics” section in the Supporting Information (SI)]. A parameter κ_1 describes how efficient the OCP^o → OCP^f conversion is (see also “Model applications” in SI). The initial concentration of [OCP^o], hereafter expressed as a fraction of [PB], is estimated to be ca. 0.3–0.6 ([PB] = 1) in WT *Synechocystis*. The initial

concentration $[\text{OCP}^0]_0$ and κ_1 yield the time-dependent concentration of photoactivated OCP^F . Decisive for NPQ induction is the encounter probability between PB and OCP^F [see Eq. (S11)]. The rate at which the binding occurs is k_1 , whereas k_2 is the rate at which the FRP detaches OCP^F from the PB core (Gwizdala et al. 2013).

Under light conditions, the minimal, maximal and variable fluorescence are termed F'_0 , F'_M and F'_V , respectively (see e.g. the review of Baker 2008). Our a priori knowledge of the fluorescence quantum yields of quenched states can help solving the problem of degeneracy: a set of

This system has a solution provided there is enough contrast in the fluorescence quantum yields between open and closed states [see Eqs. (S27), (S28)]. In that case, \mathbf{A} is invertible and we obtain an estimate for the concentration vector:

$$\hat{c} = \mathbf{A}^{-1} \times F. \quad (12)$$

Once the concentration vector has been estimated, Eq. (9) yields the estimated fraction of closed PPc2 and PSII_{free} when the high actinic light is turned on:

$$\hat{c}_0 = \frac{F_{0,\text{cyano}}^q + \hat{f}_2 \times (\phi_{\text{PPc2},o,q} - \phi_{\text{PSII},o}) + (\hat{\gamma} - 1) \times \phi_{\text{PPc2},o,q} - \hat{\gamma} \times \phi_{\text{PB},q}}{\hat{f}_2 (\phi_{\text{PPc2},o,q} + \phi_{\text{PSII},c} - \phi_{\text{PSII},o} - \phi_{\text{PPc2},c,q}) - (\hat{\gamma} - 1) \times (\phi_{\text{PPc2},c,q} - \phi_{\text{PPc2},o,q})}. \quad (13)$$

analogous equations to Eqs. (7) and (8) (also shown below for clarity) can be postulated for the quenched state. Let $F_{0,\text{cyano}}^q$ and $F_{M,\text{cyano}}^q$ be the fluorescence levels of the fully quenched states; minimal and maximal fluorescence levels then read

$$F_{0,\text{cyano}} = \gamma \times \phi_{\text{PB},u} + c_2 \times \phi_{\text{PPc2},o,u} + f_2 \times \phi_{\text{PSII},o}, \quad (7)$$

$$F_{M,\text{cyano}} = \gamma \times \phi_{\text{PB},u} + c_2 \times \phi_{\text{PPc2},c,u} + f_2 \times \phi_{\text{PSII},c}. \quad (8)$$

$$F_{0,\text{cyano}}^q = \gamma \times \phi_{\text{PB},q} + (1 - c_0) \times (c_2 \times \phi_{\text{PPc2},o,q} + f_2 \times \phi_{\text{PSII},o}) + c_0 \times (c_2 \times \phi_{\text{PPc2},c,q} + f_2 \times \phi_{\text{PSII},c}), \quad (9)$$

$$F_{M,\text{cyano}}^q = \gamma \times \phi_{\text{PB},q} + c_2 \times \phi_{\text{PPc2},c,q} + f_2 \times \phi_{\text{PSII},c}, \quad (10)$$

where we have introduced c_0 the fraction of PSII (free or bound) that is closed due to the high intensity of the NPQ-inducing light. Note that, in our model, only the species containing PB can be quenched; therefore, the PSII_{free} is not subject to NPQ during strong blue–green light exposure.

The additional condition introduced through the fully quenched state yields Eq. (10), which in combination with Eqs. (7) and (8) now builds a linear system of three equations with three unknowns. Alternatively, we can formulate the problem in a $n_s \times m$ matrix form $F = \mathbf{A} \times c$, where F and c are vectors and the matrix \mathbf{A} has n_s rows corresponding to the s light-induced states of the sample and m columns associated with the number of fluorescent species:

$$\begin{pmatrix} F_{0,\text{cyano}} \\ F_{M,\text{cyano}} \\ F_{M,\text{cyano}}^q \end{pmatrix} = \begin{pmatrix} \phi_{\text{PB},u} & \phi_{\text{PPc2},o,u} & \phi_{\text{PSII},o} \\ \phi_{\text{PB},u} & \phi_{\text{PPc2},c,u} & \phi_{\text{PSII},c} \\ \phi_{\text{PB},q} & \phi_{\text{PPc2},c,q} & \phi_{\text{PSII},c} \end{pmatrix} \times \begin{pmatrix} \gamma \\ c_2 \\ f_2 \end{pmatrix}. \quad (11)$$

Finally, Fig. S10 shows the simulated data and the fit with the respective contributions resolved. The estimated parameters are given in Table S2 (trial Q1).

Time evolution

In the example discussed above, we have made use exclusively of the data points for which a static contribution could be given: Eqs. (7) and (8) correspond to the fully unquenched state, whereas Eqs. (9) and (10) describe the fully quenched state. In both cases, the respective concentrations do not vary in time. In a PAM experiment, however, one monitors a progressive time evolution from the unquenched to the quenched state following the introduced change in light conditions. Figure 3 shows an example: The first 100 s (grey bar on top indicates dim blue light regime) correspond to the static contributions. At $t = 100$ s, the actinic light is turned on (turquoise bar on top) and saturates partly the PSII reaction centres, shifting a fraction c_0 of the PSII population from the open to the closed state (F_0 becomes F_s), regardless of the fact whether they are bound to a PB antenna or not. Concomitantly, the high actinic light triggers the photoconversion $\text{OCP}^0 \rightarrow \text{OCP}^F$ and thus the formation of quenching complexes PB– OCP^F , called C_q hereafter. C_q formation reflects in the overall decrease of fluorescence and the gradual shift within ca. 100 s towards another state characterized by the fluorescence quantum yields of the fully quenched species ($t > 200$ s) which can be satisfactorily described by either Eq. (9) or (10). Suppose we would like to know how the maximal fluorescence from the complex PPc2 evolves from the ‘unquenched’-static level described by $c_2 \cdot \phi_{\text{PPc2},c,u}$ to the ‘quenched’-static level described by




Fig. 3 Simulated data with a pulse every 20 s and noise level of 0.01. At time $t = 100$ s, strong blue-green light is turned on (indicated by the colour bars on the top). Its power is such that a fraction c_0 of the RCs are closed and the $OCP^o \rightarrow OCP^r$ conversion takes place with $\kappa_1 = 0.09 \text{ s}^{-1}$. The amount of OCP^r formed is $[OCP^r] = 0.5$ and it binds to PB with $k_1 = 0.30 \text{ s}^{-1}$. The FRP detaches the OCP bound to the PB with $k_2 = 0.003 \text{ s}^{-1}$. A fluorescence recovery region has been added: at time $t = 300$ s, the NPQ-inducing light is turned off. All RCs re-open and the $OCP^o \rightarrow OCP^r$ conversion stops ($\kappa_1 = 0$). The action of FRP can be resolved better and k_2 can be estimated ($k_2 = 0.00306 \pm 0.00007 \text{ s}^{-1}$). For all estimated parameters, see Table S2. *Black dots* simulated data points; *red* PPc2 contribution; *blue* PB_{free} contribution; *magenta* $PSII_{free}$ contribution; *grey* sum of the three contributions. Residuals are shown on top with an offset of 1300

$c_2 \cdot \phi_{PPc2,c,q}$. What we are looking for is thus an adequate expression for $c_2(t)$.

Let $F'_s(t)$ and $F'_M(t)$ be the respective levels of steady-state and maximal fluorescence at any given time t under strong blue-green illumination. The data points within the interval $100 < t < 200$ s in Fig. 3 show a time-evolving mixture of quenched and unquenched species, i.e. the expression we are interested in necessarily has the mixed form (consider, for simplicity, only the maximum fluorescence):

$$F'_{M,PPc2}(t) = c_{2,u}(t) \times \phi_{PPc2,c,u} + c_{2,q}(t) \times \phi_{PPc2,c,q}, \quad (14)$$

where of course, the sum of quenched and unquenched species yields the total amount of complexes: $c_{2,u}(t) + c_{2,q}(t) = c_2$. The equation system we need to solve to determine the time-dependence is (see “Derivation of the quenching and recovery dynamics” in SI):

$$PB'(t) = -k_1 \times PB^2(t) + (k_1 \times (PB_0 - OCP^r_0 - OCP^o_0 + OCP^o(t)) - k_2) \times PB(t) + k_2 \times (C_{q,0} + PB_0), \quad (15)$$

$$OCP^o'(t) = -\kappa_1 \times OCP^o(t) + k_3 \times (PB(t) - PB_0 + OCP^r_0 + OCP^o_0 - OCP^o(t)). \quad (16)$$

We call the set of numerical solutions to this system $Q_i(P,t)$ where the index i indicates which of the four concentration profiles the quenching function describes. We use u for unquenched PB, q for C_q , o for the orange form of OCP and r for its red form. The time-dependence can be easily expressed as the product of an initial concentration value c_j and the corresponding profile given by $Q_i(P,t)$. Furthermore, recall that the kinetic rates are defined as κ_1 light-intensity-related activation of OCP^o , k_1 OCP-binding rate, k_2 FRP-related detaching rate, and k_3 deactivation of OCP^r . Thus, the set of parameters read: $P = ([PB], [OCP^o], [OCP^r], [C_q], k_1, k_2, k_3, \kappa_1)$. We include in the SI several graphical solutions of $Q_i(P,t)$ evaluated with different arguments (Figs. S5, S6).

Let the vector $P^0 = ([PB]^0, [OCP^o]^0, [OCP^r]^0, [C_q]^0, k_1^0, k_2^0, k_3^0, \kappa_1^0)$ be a vector containing a defined set of parameters for which we obtain the function $Q_i(P^0,t)$. The time-dependent expression [given in Eq. (14)] for the maximal fluorescence $F'_M(t)$ resulting from the PPc2 species at any given time t within the dynamic region $100 < t < 200$ s would then read

$$F'_{M,PPc2}(t) = c_2 \times Q_u(P^0,t) \times \phi_{PPc2,c,u} + c_2 \times Q_q(P^0,t) \times \phi_{PPc2,c,q}. \quad (17)$$

Therefore, the whole expression for $F'_M(t)$ in this three-component example is given by

$$F'_M(t) = \gamma \times (Q_u(P^0,t) \times \phi_{PB,u} + Q_q(P^0,t) \times \phi_{PB,q}) + c_2 \times (Q_u(P^0,t) \times \phi_{PPc2,c,u} + Q_q(P^0,t) \times \phi_{PPc2,c,q}) + f_2 \times \phi_{PSII,c}. \quad (18)$$

An analogous equation can be written for the time-dependent Eq. (9).

Modelling the time evolution also helps clarifying the following: a *fully* quenched state [see Eq. (10)] does *not* mean that all the PBs present in the sample are quenched; rather the fraction of OCP that gets activated dynamically equilibrates the system in this *fully* quenched state. Notice Fig. S8 in the SI, in which it is illustrated that an increasing OCP/PB ratio affects the equilibrium level at $t \rightarrow \infty$.

Estimating OCP-related parameters

In addition to resolving the different species-related contributions, we also gain insight into NPQ kinetics. Since there is a gradual equilibration between the unquenched

and the quenched state, the data points in the region $t > 100$ s of Fig. 3 deliver information over the rates k_1 , k_2 and the amount of OCP^o present in the cells. Table S2 contains estimated parameters in different trials. Trials Q1–Q4 (Q indicating that next to the F_0 region, only quenching region data are used, but not the recovery region) were performed on the simulated data shown in Fig. S10. In trial Q1, no kinetic parameters were freed; in trial Q2, we free the OCP^r–PB binding rate k_1 . Note that the t values slightly change for all the estimated parameters, but in principle, all of them have been estimated reliably. This does not hold true for trials Q3 (free parameters: k_1 and k_2) and Q4 (free parameters: k_1 , k_2 and OCP^o) where we stepwise increase the number of parameters we want to estimate. In particular, the reliability with which the FRP-related detaching rate k_2 is estimated drastically drops in these two last trials. The conclusion is, therefore, that there is not enough information to estimate all of the seven parameters accurately, the detaching rate k_2 being the most challenging to estimate correctly.

In order to add valuable information that allows all parameters, including k_2 , to be estimated, we simulate a new region for $t > 300$ s where the sample is exposed to dim blue light (grey bar on top) and k_1 becomes negligible (see Fig. 3). In this light regime, the amount of formed OCP^r is negligible and the quenching complexes are no longer formed. Hence, a region of fluorescence recovery delivers additional information (trial Q + R) so that also k_2 can be estimated reliably (see Table S2 for t values).

Adding PSI_{free} as a third component

Above we have chosen the PSII_{free} contribution to illustrate the problem of degeneracy. Instead, we could have chosen any other realistic contribution, for instance, a PSI-related contribution. Due to the greater number of PSI than PSII in *Synechocystis* (Moal and Lagoutte 2012), the PSI contribution, despite the short PSI fluorescence lifetime, is not negligible. Let the concentration of free PSI trimers, f_1 , be β times greater than the PSII-dimer concentration c_2 . Furthermore, we will simplify the problem by considering PB to be a PSII-specific antenna, i.e. no PSI complex has any PB attached to it (PSI_{free}). Analogous equations to (7)–(10) can then be written (see “The PSI contribution” in the SI). Notice that, in Eq. (S30), PSI is assumed not to adopt any closed or open states or to undergo quenching (in this example, PB does not attach to PSI). Figure S11 shows the simulated data and the fit with the PB_{free}, PPc2 and PSI_{free} contributions, respectively, resolved. The constant PSI_{free} contribution, present in all conditions, correlates strongly with the *scale* and NPQ parameters and cannot be accurately estimated due to numerical unidentifiability. Hence, it is necessary to make further assumptions based on

independent measurements in order to obtain interpretable results.

A case study

Figure 4a shows experimental data from a PAM experiment carried out on whole cells of wild-type *Synechocystis* (Jallet et al. 2012) that has been fitted using our model with the following components: PPc2, PB_{free} and PSI_{free}. After analysis, the PSII_{free} contribution of these samples turned out to be negligible. The PSI/PSII proportionality factor β has been set to $\beta = 3.6$ based on *Synechocystis* stoichiometry published by Moal and Lagoutte (2012). The grey curve fits the data points (shown in black). This grey curve is the sum of all other contributions: the PPc2 in red, the PSI_{free} in cyan and PB_{free} in blue. Residuals are shown in the upper part of the figure. The estimated parameters are shown in Table 2 and in more detail in Table S3. Notice that, during the experiment, the light intensity is manually adjusted: turning the strong blue light on and off is modelled as being instantaneous and therefore it cannot possibly describe the data accurately in the transition regions. For this reason, the contributions to the error analysis of the data points lying in the respective transition regions have been arbitrarily weighted down to one tenth.

In addition to WT, mutants that lack the core terminal emitter subunits allophycocyanin D (Δ ApcD) or allophycocyanin F (Δ ApcF), or both (Δ ApcDF) have been measured. The difference in free energy between PB and PSII is smaller in WT than in the mutants that lack APC680 pigments. However, we assume the same set of quantum yields (Table 1). This implies that PB either transfers to PS with a certain rate or not (PB_{free}). Target analysis of streak camera measurements is needed to test this assumption.

The results for the mutants Δ ApcD, Δ ApcF and Δ ApcDF are shown in Fig. 4b–d. The relative amount of PB_{free} in each sample increased in the order WT \rightarrow Δ ApcD \rightarrow Δ ApcF \rightarrow Δ ApcDF. This rationalizes two observations: first, the F_0 -level also increases in the same order even though the amount of Chl *a* remained the same. This means that the mutations all affected the energy transfer to the RCs just as observed by Bryant (1991) and Dong et al. (2009). And second, after 200 s of intense blue–green illumination, the steady-state fluorescence $F'_s(t)$ in the mutants is quenched below $F_{0,\text{cyano}}$ in dim blue light. Indeed, this can only be explained by means of a large amount of quenched uncoupled PB.

The parameter related to fluorescence recovery, k_2 , seems not to be affected by an increasing amount of PB_{free} but by the presence (or absence) of ApcF. Both WT and the Δ ApcD mutants have indeed similarly slower fluorescence recovery rates than the two mutants that lack ApcF. In




Fig. 4 Fit of experimental PAM measurements performed on whole cells of WT *Synechocystis* (a) and mutants thereof: Δ ApcD (b), Δ ApcF (c), Δ ApcDF (d). Colour bars on the top of each panel indicate the light regime: dark (black), 30 μ E (grey) and 1400 μ E (turquoise). All estimated parameters are collated in Table 2. Black dots experimental data points; red PPc2 contribution; blue PB_{free} contribution; cyan PSI_{free} contribution; grey sum of all contributions. Residuals (grey) are shown in each panel with an offset

Table 2 Estimated parameters from experimental PAM measurements performed on whole cells of WT *Synechocystis* and mutants thereof 21

	WT	Δ ApcD	Δ ApcF	Δ ApcDF
γ	0.034	0.059	0.072	0.131
c_0	0.606	0.564	0.571	0.577
scale	13899.6	14314.8	14838.5	13942.9
k_1	0.121	0.243	0.302	0.451
k_2	0.0096	0.0068	0.019	0.018
OCP ₀ ^o	0.61	0.64	0.53	0.46

The amount of PSI_{free} has been fixed (see Table S3). Bold parameters indicate the most important results

contrast, k_1 does increase in the order: WT \rightarrow Δ ApcD \rightarrow Δ ApcF \rightarrow Δ ApcDF suggesting that OCP gets quicker attached to the PB core. Thus, the lack of the ApcD or ApcF could affect the ability of the PB to strongly bind to the membrane and to efficiently functionally couple to the photosystems resulting therefore in a more important amount of PB_{free} (see definition in ‘A model to resolve several contributions to a cyanobacterial PAM-signal’) in single-mutated systems than in WT, the greatest amount of PB_{free} being that of the double mutant Δ ApcDF. Figure 5 depicts the correlation between PB_{free} and k_1 . It would be indeed consistent with the idea that the less tightly bound the PB is to the membrane, the easier it gets for external proteins just like OCP and FRP to reach the binding site.

An alternative interpretation is that the mutations affect the rate of energy transfer from PB to PSII. In that case, a different set of quantum yields (cf. Table 1) for each of the mutants will be needed, based upon target analysis of




Fig. 5 Correlation between the estimated parameters γ and k_1 in the different samples

streak camera measurements. Such measurements can also demonstrate the presence of increased amounts of uncoupled PB with a 1.6 ns lifetime. These measurements and analyses are in progress. Further information can be gained from spectrally resolved fluorescence induction (Kana et al. 2012; Kirilovsky et al. 2014).

Note that the residuals of all samples are acceptable except for one systematic pattern: during the very first seconds of the measurement, the fluorescence is collected in darkness (black bar on top of each panel). *Synechocystis* cells are known to be in state 2, where PSI gets more excitation energy. The transition from darkness to dim blue light draws a characteristic feature in the PAM trace: the relative distribution of excitation energy from the PB to both of the photosystems changes and more of the energy will be transferred to PSII (state 1) hence why a subtle increase in F_M and also in F_0 is observed (F_0 also varies due to a small fraction of photosystems being closed by the dim blue light). Since our model does not include this relative change that affects the concentration c_2 , it systematically fails to match both F_M and the F_0 levels. The best fit is the one of the mutant Δ ApcD—a mutant for which state transitions have been reported to be severely impaired (Dong et al. 2009) and can therefore be modelled somewhat better by a model that implicitly assumes the cells to be locked in one state.

Concluding remarks

We have presented a model for cyanobacterial PAM-traces taking into account the phycobilin-related contribution. The main feature of our model is that several fluorescent species can be resolved and their concentrations be estimated. This is remarkable because the traditional use of a PAM experiment has been to determine the dynamic changes of fluorescence quantum yields of species whose concentrations were previously known. Besides, this new approach opens up the possibility to the analysis of quenching curves in cyanobacteria making use of the knowledge already developed for PAM signals in plants.

The energy-dependent component of NPQ in cyanobacteria has also been modelled. This allowed typical quenching curves of experiments tracking fluorescence carried out in vitro and in vivo to be parameterized and analysed. The full dynamics could be reproduced: the fast opening and closing dynamics of RCs due to short saturation pulses, OCP-driven NPQ and FRP-assisted fluorescence recovery kinetics. Our model was used to quantify OCP-related parameters while resolving the different components and determining their time-dependent concentrations in the sample. Subsequently, the following

conclusions have been drawn: ApcD and ApcF play a role in tightly binding the PB to the thylakoid membrane. Mutants where these pigments were missing contained ca. 3 % more functionally uncoupled phycobilisomes. Besides, the estimated OCP-attaching (and detaching) rates consistently vary from mutant to mutant providing these experimental results with a model-based interpretation. However, the interpretation suggested by these results does not exclude the scenario where PBs lacking ApcD and ApcF transfer energy less efficiently to the PS.

This model can be used for systematically assessing the emissive species' content in samples that lack any of the (or both) photosystems, have been grown under different light conditions or even those which have undergone targeted stress, i.e. iron or copper deprivation. In a broader context, our model is a potential tool for all cyanobacterial photosynthesis studies: from basic research in photosynthesis to environmental studies in which cyanobacterial populations in seas or lakes are monitored using a PAM instrument.

Acknowledgments The authors gratefully acknowledge Dr. Ben Bakker for advises in mathematical issues and Dr. Gert Schansker for critically reading the article. The research is performed as part of the BioSolar Cells research programme, sponsored by the Dutch Ministry of Economic Affairs. This work is part of the research programme of the Foundation for Fundamental Research on Matter (FOM), which is part of the Netherlands Organisation for Scientific Research (NWO). MG, IHMV and RvG acknowledge financial support of the European Research Council (Advanced Grant Proposal 267333 (PHOTPROT) to RvG). RvG was further supported by the Netherlands Organization for Sciences, Council of Chemical Sciences (NWO-CW) via a TOP-Grant (700.58.305), and by the EU FP7 Project PAPERETS (GA 323901). RvG gratefully acknowledges his Academy Professor grant from the Netherlands Royal Academy of Sciences (KNAW). MG acknowledges financing from EMBO (LTF).

Open Access This article is distributed under the terms of the Creative Commons Attribution 4.0 International License (<http://creativecommons.org/licenses/by/4.0/>), which permits unrestricted use, distribution, and reproduction in any medium, provided you give appropriate credit to the original author(s) and the source, provide a link to the Creative Commons license, and indicate if changes were made.

References

- Adir N (2005) Elucidation of the molecular structures of components of the phycobilisome: reconstructing a giant. *Photosynth Res* 85:15–32. doi:10.1007/s11120-004-2143-y
- Arteni AA, Ajlani G, Boekema EJ (2009) Structural organisation of phycobilisomes from *Synechocystis* sp strain PCC6803 and their interaction with the membrane. *Biochim Biophys Acta* 1787:272–279. doi:10.1016/j.bbabi.2009.01.009
- Baker NR (2008) Chlorophyll fluorescence: a probe of photosynthesis in vivo. *Annu Rev Plant Biol* 59:89–113. doi:10.1146/annurev-arplant.59.032607.092759
- Boulard C, Wilson A, D'Haene S, Kirilovsky D (2010) Identification of a protein required for recovery of full antenna capacity in OCP-related photoprotective mechanism in cyanobacteria. *Proc*

- Natl Acad Sci USA 107:11620–11625. doi:[10.1073/pnas.1002912107](https://doi.org/10.1073/pnas.1002912107)
- Bryant DA (1991) Cyanobacterial phycobilisomes: progress toward complete structural and functional analysis via molecular genetics. In: Bogorad L, Vasil IK (eds) *The photosynthetic apparatus: molecular biology and operation*, vol 7. Academic Press, San Diego, pp 257–300
- Bryant D, Guglielmi G, de Marsac N, Castets A-M, Cohen-Bazire G (1979) The structure of cyanobacterial phycobilisomes: a model. *Arch Microbiol* 123:113–127. doi:[10.1007/BF00446810](https://doi.org/10.1007/BF00446810)
- Butler WL (1978) Energy distribution in the photochemical apparatus of photosynthesis. *Annu Rev Plant Physiol* 29:345–378
- Campbell D, Hurry V, Clarke AK, Gustafsson P, Oquist G (1998) Chlorophyll fluorescence analysis of cyanobacterial photosynthesis and acclimation. *Microbiol Mol Biol Rev* 62:667–683
- David L, Marx A, Adir N (2011) High-resolution crystal structures of trimeric and rod phycocyanin. *J Mol Biol* 405:201–213. doi:[10.1016/j.jmb.2010.10.036](https://doi.org/10.1016/j.jmb.2010.10.036)
- Demmig B, Winter K, Kruger A, Czygan FC (1987) Photoinhibition and zeaxanthin formation in intact leaves: a possible role of the xanthophyll cycle in the dissipation of excess light energy. *Plant Physiol* 84:218–224. doi:[10.1104/pp.84.2.218](https://doi.org/10.1104/pp.84.2.218)
- Dong C, Tang A, Zhao J, Mullineaux CW, Shen G, Bryant DA (2009) ApcD is necessary for efficient energy transfer from phycobilisomes to photosystem I and helps to prevent photoinhibition in the cyanobacterium *Synechococcus* sp. PCC 7002. *Biochim Biophys Acta* 1787:1122–1128. doi:[10.1016/j.bbabi.2009.04.007](https://doi.org/10.1016/j.bbabi.2009.04.007)
- Ebenhöh O, Houwaart T, Lokstein H, Schleder S, Tirok K (2011) A minimal mathematical model of nonphotochemical quenching of chlorophyll fluorescence. *Biosystems* 103:196–204. doi:[10.1016/j.biosystems.2010.10.011](https://doi.org/10.1016/j.biosystems.2010.10.011)
- Fork DC, Satoh K (1986) The control by state transitions of the distribution of excitation energy in photosynthesis. *Annu Rev Plant Physiol* 37:335–361
- Funk C, Schroder WP, Napiwotzki A, Tjus SE, Renger G, Andersson B (1995) The PSII-S protein of higher-plants—a new-type of pigment-binding protein. *Biochemistry* 34:11133–11141. doi:[10.1021/bi00035a019](https://doi.org/10.1021/bi00035a019)
- Glazer AN, Lundell DJ, Yamanaka G, Williams RC (1983) The structure of a simple phycobilisome. *Ann Microbiol* B134:159–180. doi:[10.1016/s0769-2609\(83\)80103-3](https://doi.org/10.1016/s0769-2609(83)80103-3)
- Gorbanov MY, Kuzminov FI, Fadeev VV, Kim JD, Falkowski PG (2011) A kinetic model of non-photochemical quenching in cyanobacteria. *Biochim Biophys Acta* 1807:1591–1599. doi:[10.1016/j.bbabi.2011.08.009](https://doi.org/10.1016/j.bbabi.2011.08.009)
- Gwizdala M, Wilson A, Kirilovsky D (2011) In vitro reconstitution of the cyanobacterial photoprotective mechanism mediated by the Orange Carotenoid Protein in *Synechocystis* PCC 6803. *Plant Cell* 23:2631–2643. doi:[10.1105/tpc.111.086884](https://doi.org/10.1105/tpc.111.086884)
- Gwizdala M, Wilson A, Omairi-Nasser A, Kirilovsky D (2013) Characterization of the *Synechocystis* PCC 6803 Fluorescence Recovery Protein involved in photoprotection. *Biochim Biophys Acta* 1827:348–354. doi:[10.1016/j.bbabi.2012.11.001](https://doi.org/10.1016/j.bbabi.2012.11.001)
- Härtel H, Lokstein H (1995) Relationship between quenching of maximum and dark-level chlorophyll fluorescence in vivo: dependence on Photosystem II antenna size. *Biochim Biophys Acta* 1228:91–94. doi:[10.1016/0005-2728\(94\)00172-2](https://doi.org/10.1016/0005-2728(94)00172-2)
- Holzwarth AR, Lenk D, Jahns P (2013) On the analysis of non-photochemical chlorophyll fluorescence quenching curves: I. Theoretical considerations. *Biochim Biophys Acta* 1827:786–792. doi:[10.1016/j.bbabi.2013.02.011](https://doi.org/10.1016/j.bbabi.2013.02.011)
- Jallet D, Gwizdala M, Kirilovsky D (2012) ApcD, ApcF and ApcE are not required for the Orange Carotenoid Protein related phycobilisome fluorescence quenching in the cyanobacterium *Synechocystis* PCC 6803. *Biochim Biophys Acta* 1817:1418–1427. doi:[10.1016/j.bbabi.2011.11.020](https://doi.org/10.1016/j.bbabi.2011.11.020)
- Kaňa R, Kotabová E, Komárek O, Šedivá B, Papageorgiou GC, Govindjee, Prášil O (2012) The slow S to M fluorescence rise in cyanobacteria is due to a state 2 to state 1 transition. *Biochim Biophys Acta* 1817:1237–1247. doi:[10.1016/j.bbabi.2012.02.024](https://doi.org/10.1016/j.bbabi.2012.02.024)
- Kirilovsky D (2007) Photoprotection in cyanobacteria: the orange carotenoid protein (OCP)-related non-photochemical-quenching mechanism. *Photosynth Res* 93:7–16. doi:[10.1007/s11120-007-9168-y](https://doi.org/10.1007/s11120-007-9168-y)
- Kirilovsky D (2014) Modulating energy arriving at photochemical reaction centers: orange carotenoid protein-related photoprotection and state transitions. *Photosynth Res*. doi:[10.1007/s11120-014-0031-7](https://doi.org/10.1007/s11120-014-0031-7)
- Kirilovsky D, Kaňa R, Prášil O (2014) Mechanisms modulating energy arriving at reaction centers in cyanobacteria. In: Demmig-Adams B, Garab G, Adams W III, Govindjee (eds) *Non-photochemical quenching and energy dissipation in plants, algae and cyanobacteria*. Springer, New York, pp 471–501
- Krause GH, Weis E (1991) Chlorophyll fluorescence and photosynthesis—the basics. *Annu Rev Plant Phys* 42:313–349. doi:[10.1146/annurev.pp.42.060191.001525](https://doi.org/10.1146/annurev.pp.42.060191.001525)
- Laisk A, Oja V, Rasulov B, Eichelmann H, Sumberg A (1997) Quantum yields and rate constants of photochemical and nonphotochemical excitation quenching (experiment and model). *Plant Physiol* 115:803–815
- Li XP, Björkman O, Shih C, Grossman AR, Rosenquist M, Jansson S, Niyogi KK (2000) A pigment-binding protein essential for regulation of photosynthetic light harvesting. *Nature* 403:391–395. doi:[10.1038/35000131](https://doi.org/10.1038/35000131)
- MacColl R (1998) Cyanobacterial phycobilisomes. *J Struct Biol* 124:311–334. doi:[10.1006/jsbi.1998.4062](https://doi.org/10.1006/jsbi.1998.4062)
- Moal G, Lagoutte B (2012) Photo-induced electron transfer from photosystem I to NADP(+): characterization and tentative simulation of the in vivo environment. *Biochim Biophys Acta* 1817:1635–1645. doi:[10.1016/j.bbabi.2012.05.015](https://doi.org/10.1016/j.bbabi.2012.05.015)
- Mullineaux C, Allen J (1990) State 1-State 2 transitions in the cyanobacterium *Synechococcus* 6301 are controlled by the redox state of electron carriers between Photosystems I and II. *Photosynth Res* 23:297–311. doi:[10.1007/BF00034860](https://doi.org/10.1007/BF00034860)
- Papageorgiou GC, Govindjee (eds) (2004) *Chlorophyll a fluorescence. Advances in Photosynthesis and Respiration*, vol 19. Springer, Dordrecht. doi:[10.1007/978-1-4020-3218-9](https://doi.org/10.1007/978-1-4020-3218-9)
- Papageorgiou GC, Tsimilli-Michael M, Stamatakis K (2007) The fast and slow kinetics of chlorophyll *a* fluorescence induction in plants, algae and cyanobacteria: a viewpoint. *Photosynth Res* 94:275–290. doi:[10.1007/s11120-007-9193-x](https://doi.org/10.1007/s11120-007-9193-x)
- Schreiber U, Endo T, Mi HL, Asada K (1995) Quenching analysis of chlorophyll fluorescence by the saturation pulse method—particular aspects relating to the study of eukaryotic algae and cyanobacteria. *Plant Cell Physiol* 36:873–882
- Sutter M et al (2013) Crystal structure of the FRP and identification of the active site for modulation of OCP-mediated photoprotection in cyanobacteria. *Proc Natl Acad Sci USA* 110:10022–10027. doi:[10.1073/pnas.1303673110](https://doi.org/10.1073/pnas.1303673110)
- Tian L, van Stokkum IHM, Koehorst RBM, Jongerijs A, Kirilovsky D, van Amerongen H (2011) Site, rate, and mechanism of photoprotective quenching in cyanobacteria. *J Am Chem Soc* 133:18304–18311. doi:[10.1021/ja206414m](https://doi.org/10.1021/ja206414m)
- Tian L, Gwizdala M, van Stokkum IHM, Koehorst RBM, Kirilovsky D, van Amerongen H (2012) Picosecond kinetics of light harvesting and photoprotective quenching in wild-type and mutant phycobilisomes isolated from the cyanobacterium *Synechocystis* PCC 6803. *Biophys J* 102:1692–1700. doi:[10.1016/j.bpj.2012.03.008](https://doi.org/10.1016/j.bpj.2012.03.008)
- Tian L, Farooq S, van Amerongen H (2013) Probing the picosecond kinetics of the photosystem II core complex in vivo. *Phys Chem Chem Phys* 15:3146–3154. doi:[10.1039/c3cp43813a](https://doi.org/10.1039/c3cp43813a)

- van Grondelle R (1985) Excitation energy transfer, trapping and annihilation in photosynthetic systems. *Biochim Biophys Acta* 811:147–195. doi:[10.1016/0304-4173\(85\)90017-5](https://doi.org/10.1016/0304-4173(85)90017-5)
- van Grondelle R, Dekker JP, Gillbro T, Sundstrom V (1994) Energy transfer and trapping in photosynthesis. *Biochim Biophys Acta* 1187:1–65. doi:[10.1016/0005-2728\(94\)90166-X](https://doi.org/10.1016/0005-2728(94)90166-X)
- Vernotte C, Astier C, Olive J (1990) State 1-state 2 adaptation in the cyanobacteria *Synechocystis* PCC 6714 wild type and *Synechocystis* PCC 6803 wild type and phycocyanin-less mutant. *Photosynth Res* 26:203–212
- Wilson A, Ajlani G, Verbavatz JM, Vass I, Kerfeld CA, Kirilovsky D (2006) A soluble carotenoid protein involved in phycobilisome-related energy dissipation in cyanobacteria. *Plant Cell* 18:992–1007. doi:[10.1105/tpc.105.040121](https://doi.org/10.1105/tpc.105.040121)
- Wilson A, Boulay C, Wilde A, Kerfeld CA, Kirilovsky D (2007) Light-induced energy dissipation in iron-starved cyanobacteria: roles of OCP and IsiA proteins. *Plant cell* 19:656–672. doi:[10.1105/tpc.106.045351](https://doi.org/10.1105/tpc.106.045351)
- Wilson A et al (2008) A photoactive carotenoid protein acting as light intensity sensor. *Proc Natl Acad Sci USA* 105:12075–12080. doi:[10.1073/pnas.0804636105](https://doi.org/10.1073/pnas.0804636105)
- Wraight CA, Crofts AR (1970) Energy-dependent quenching of chlorophyll-a fluorescence in isolated chloroplasts. *Eur J Biochem* 17:319–323. doi:[10.1111/j.1432-1033.1970.tb01169.x](https://doi.org/10.1111/j.1432-1033.1970.tb01169.x)
- Zaks J, Amarnath K, Kramer DM, Niyogi KK, Fleming GR (2012) A kinetic model of rapidly reversible nonphotochemical quenching. *Proc Natl Acad Sci USA* 109:15757–15762